PROJECT>Parkway Crossing/Summit Development BYU Student Housing

Orem, Utah





PROJECT START DATE:

June 2005

PROJECT COMPLETION

DATE: June 2006

PROJECT DESCRIPTION:

1,080,000 square feet of One Coat Fiberglass Reinforced Stucco installed over 1" polystyrene foam spray applied at ½" thickness. The project consisted of five multi-unit buildings. QUIKRETE's one-hour fire rating over the combination of OSB and EPS foam was a key element in the selection of QUIKRETE One-coat Fiberglass Reinforced Stucco.

CONTRACTOR:

Sahara Construction

Sub-Contractor: Nicolson Construction

QUIKRETE® PRODUCTS USED:

•3000 lb One Coat Fiberglass
Reinforced Stucco-Sanded:1,440 bulk bags



One Coat Fiberglass Reinforced
Stucco (FRS) >> Product No.
1200-80-Sanded, 1216-93-Concentrated







