PROJECT > Nobelstown Bridge Structural Repair of Bridge Columns & Pier Hammerheads Allegheny County, PA





PROJECT START DATE: September 2008

PROJECT COMPLETION DATE: November 2008

PROJECT DESCRIPTION:

Full-depth monolithic, vertical and overhead structural repairs to severely deteriorated bridge columns and pier hammerheads. Shotcrete MS with corrosion inhibitor was applied at up to 3" thick in a single pass with virtually zero rebound. Shotcrete MS Achieves over 9000 psi compressive strength in 28 days.

CONTRACTOR: Sofis Company inc.

QUIKRETE® PRODUCT USED:

• 3000 lb. bulk bags Shotcrete MS: 99 bags



Shotcrete MS>> Product No. 1229







