

PROJECT > Jefferson Street Ramp

Harrisburg, PA



PROJECT DESCRIPTION:

This project was a complete rehabilitation of the ramp, including complete deck replacement and sidewalks. Shotcrete cosmetic repairs of the face and Shotcrete Structural repairs on the Arches, Piers and overhead. Since this project, a new Shotcrete Repair Specification was written by RCS Consulting. This spec will be added to the 408 Spec that is used through the State for a guideline for all types of highway repairs.

CONTRACTOR:

Jay Fulkroad & Sons
Sub-Contractor: RCS Consulting

PROJECT START DATE:
May 2005

PROJECT COMPLETION DATE: July 2006

QUIKRETE® PRODUCTS USED:

- 3000 lb Shotcrete MS: 96 bags
- 50 lb Non-shrink Precision Grout: 63 bags



Shotcrete >>
Product No. 1228-21



Non-Shrink Precision Grout >>
Product No. 1585-00

