

PROJECT > Omni Nashville Hotel

Type S Mortar, Type N Mortar
Nashville, TN



PROJECT DESCRIPTION:

The 800-room Omni Nashville Hotel combines the city's vibrant music culture with a vast repertoire of sophisticated amenities including fine dining, an entertainment venue and a rooftop deck with a pool to create a one-of-a-kind luxury hotel experience. Located in SoBro (South of Broadway district) across from the 2.1 million square foot Music City Center and attached to the Country Music Hall of Fame

and Museum®, the Omni Nashville Hotel serves as the premier downtown accommodation for everyone from visiting tourists to celebrities to local residents. Wasco Inc. incorporated natural materials, exposed steel and regional limestone to deliver a modern look while still reflecting the city's distinct and authentic character. Nearly 80-3,000 lb bulk bags of QUIKRETE® Type S Mortar were used to lay the foundation blocks and 60-3,000 lb bulk bags of QUIKRETE® Type N Mortar in custom dark buff helped accent interior and exterior stone and brick work. In addition, the use of a bulk mortar silo system enhanced productivity and reduced labor costs on the project.

QUIKRETE® Mortar (Types S, N, & M) is a high strength commercial grade dry pre-blended mixture of sand and cements specially designed for building and reinforcing walls made of brick, block or stone. It meets the requirements of ASTM C270 types S, N, or M.

GENERAL CONTRACTOR: Brasfield and Gorrie

SUB CONTRACTOR: Wasco Inc.

PROJECT START DATE: June 2013

PROJECT COMPLETION DATE: October 2013

QUIKRETE® PRODUCTS USED:

- 3,000 lb QUIKRETE® Type S Mortar:
78 bulk bags
- 3,000 lb QUIKRETE® Type N Mortar:
60 bulk bags

