

# PROJECT > 3rd Recruit Training Battalion Complex

Bulk Mortar & Core Fill Grout  
Parris Island, SC



## PROJECT DESCRIPTION:

In 2009, US Marine Officials approved the construction of five new barracks to serve as homes for recruits and personnel within the 3rd battalion. Initially a 2 year project, the construction was fast tracked with a completion target of 12 months.

The use of QUIKRETE® Bulk Mortar, Core Fill Grout and SpecMix® Mortar Delivery Silos were instrumental in helping Walton Construction, general contractor and Bremer Concrete & Masonry, Inc., sub contractor, meet the aggressive construction schedule. QUIKRETE® Pre-blended Bulk Mortar improved product consistency, jobsite safety and productivity.

## PROJECT START DATE:

July 2009

## PROJECT COMPLETION DATE:

July 2010

## GENERAL

**CONTRACTOR:** Walton Construction

## SUB

**CONTRACTOR:** Bremer Concrete & Masonry, Inc.



**QUIKRETE® Mason Mix Type "S" >>**  
Product No. 1136-80



**QUIKRETE® Mason Mix Colored Formula Type "S" >>**  
Product No. 1136-71



**QUIKRETE® Core-Fill Grout - Coarse >>**  
Product No. 1585-07

## QUIKRETE® PRODUCTS USED:

- 3,000 lb Type "S" Mortar - Rose : 2,846 bulk bags
- 3,000 lb Type "S" Mortar - Gray : 476 bulk bags
- 3,000 lb Core-Fill Grout - Coarse : 320 bulk bags

