

PROJECT > Mountain Wind Farm Wind Turbine Base Grouting

Ft. Bridger, WY



PROJECT START DATE:

July, 2007

PROJECT COMPLETION

DATE: March 2008

PROJECT DESCRIPTION:

Non-Shrink Precision Grout was used for grouting 29 wind turbine bases in Phase I of the Mountain Wind Farm project. Phase II will include 29 additional wind turbines. Turbine pedestal bases are 55 ft. x 55 ft. Turbine footings are 17 ft. in diameter.

CONTRACTOR: RES America

SUBCONTRACTOR: Siteworks

QUIKRETE® PRODUCTS USED:

- 50 lb. Non-Shrink Precision Grout: 1120 bags



Non-Shrink Precision Grout >>
Product No. 1585-00

